BRUHAT BANGALORE MAHANAGARA PALIKE

MODIFIED APPROVED SCHEDULE - B

Name of the work:- Improvements to road, drain and footpath in main and cross roads of Sahakarangara D Block in ward no. 08 Kodigehalli.

Sl. No.	Approved Qty.	Description	Unit	Rates	
				Executive Engineer, KRIDL	
				In Figures	In Words
1	2702.97	Removing and refixing stone slabs of drains and pointing in CM (1:3) Page No. 25 / Item No. 5.33, PWD SR 2016-17	Sqm	80.56	Rupees Eighty and Fifty Six Paise Only
2	483.03	KSRRB 300 - Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 Page No. 142 / Item No. 19.10, PWD SR 2016-17	Cum	86.92	Rupees Eighty Six and Ninety Two Paise Only
3	81.75	KSRB 4-1.2 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No. 12/I.No. 4.2 of CSR 2016-17)	Cum	5348.76	Rupees Five Thousand Three Hundred Forty Eight and Seventy Six Paise Only
4	511.20	KSRB 5-11 : Providing and constructing load bearing wall with solid concrete blocks of size 400x200x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 5.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 Page No. 25 / Item No. 5.27.1, PWD SR 2016-17	Sqm	993.22	Rupees Nine Hundred Ninety Three and Twenty Two Paise Only
5	511.20	KSRB 5-11 : Providing and constructing non load bearing wall with solid concrete blocks of size 400x100x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 Page No. 25 / Item No. 5.28, PWD SR 2016-17	Sqm	758.96	Rupees Seven Hundred Fifty Eight and Ninety Six Paise Only
6	12.15	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 Page No. 13 / Item No. 5.9, PWD SR 2016-17	Cum	5305.30	Rupees Five Thousand Three Hundred Five and Thirty Paise Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the contractor

22/12

Executive Engineer

	Approved Qty.	Description	Unit	Rates	
				Executive Engineer, KRIDL	
				In Figures	In Words
7	57.11	KSRB 4.2.7 : Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintles and beams retaining walls, return walls, walls (any thickness) including attached pilasters, columns, ,pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1, 4.6 Page No. 13 / Item No. 4.12, PWD SR 2016-17	Cum	6749.02	Rupees Six Thousand Seven Hundred Forty Nine and Two Paise Only
8	27.00	KSRB 15.1.1 Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 113 / Item No. 15.1, PWD SR 2016-17	Sqm	174.90	Rupees One Hundred Seventy Four and Ninety Paise Only
9	517.59	Providing granite slabs of selected quality roughly dressed havinf a size of 10 cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete. Page No. 25 / Item No. 5.31.2, PWD SR 2016-17	Sqm	825.74	Rupees Eight Hundred Twenty Five and Seventy Four Paise Only
10	2874.00	KSRB 5-9 : Providing chamfering edges to stone slab 2.5 cms. wide as per specifications. (only chamfered length shall be recorded) KBS 5.1.13 Page No. 24 / Item No. 5.22, PWD SR 2016-17	Mtr	37.10	Rupees Thirty Seven and Ten Paise Only
11	2874	Machine cutting (Data rates)	Mtr	60.00	Rupees Sixty Only
12	517.59	KSRB 5-8.1 : Providing one line dressing to granite stone slab / granite stone masonry as per specifications .KBS 5.1.13	Sqm	577.70	Rupees Five Hundred Seventy Seven and Seventy Paise Only
13	2439	Providing and fixing pre cast solid concrete kerb stones of size 450x200x400 mm made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting ete., complete. Page No. 25 / Item No. 5.29.10, PWD SR 2016-17	Nos	385.84	Rupees Three Hundred Eighty Five and Eighty Four Paise Only
14	549	KSRB 15-19.1 : Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications. Page No. 122 / Item No. 15.80, PWD SR 2016-17	Sqm	27.56	Rupees Twenty Seven and Fifty Six Paise Only
15	549	KSRB 15-19.2 : Providing and applying spray painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications. Page No. 122 / Item No. 15.81, PWD SR 2016-17	Sqm	69.96	Rupees Sixty Nine and Ninety Six Paise Only

Signature of the contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

22/12

Executive Engineer

22/12

.	Approved Qty.	Description	Unit	Rates Executive Engineer, KRIDL	
				In Figures	In Words
16	0.51	KSRRB M300- Wrought iron and mild steel welded work KSRRB M300-18. Wrought iron and mild steel welded work (using angles, square bars, tees and channel grills, grating frames, gates and tree guards of any size and design etc. including cost of screens and welding rods or bolts and nuts complete fixed in position but without the cost of excavation and concrete for fixing which will be paid separately complete as per specifications. (25 kg per sq mtr) Page No. 15 / Item No. 19.97, PWD SR 2016-17	Qntl	6711.92	Rupees Six Thousand Seven Hundred Eleven and Ninety Two Paise Only
17	783.03	A) KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH -100/ Chapter 1 (Page No. 132 / Item No. 17.1) Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 10.00 Km etc complete as per specifications and directions of engineer in charge of the work	Cum	106.00	Rupees One Hundred Six Only
18	230.04	Providing and fixing 10 cm thick pre cast reinforced concrete slab as per design and drawing material cost, transportation, hire charges of machinery complete with all lead and lift conveyance charges labour charges inclusive of cost of all materials	Sqm	1777.75	Rupees One Thousand Seven Hundred Seventy Seven and Seventy Five Paise Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer 22/12
Byarayanapura Division
BBMP, Bangalore - 92

22/12